

ITEM	PD cost (excl VAT)
Main hall area	
Remove fire hose in main hall area and make good	122.00
Remove plywood panels in floor (3) and cut and fit t&g pine boarding in widths to match existing and apply stain finish	579.00
Cut and fit MDF behind 10 radiators in hall (as PA drawing) fit shelf behind radiators and finish with emulsion paint to match existing colour	694.00
Hack off plaster each side of emergency exit doors treat wall behind, fit eml, replaster and redecorate	340.00
Erect scaffold to each side of hall for access to panels in roof, cut and fit 12mm t&g panels over each light incl battens, fit sounds absorbent material in opening. Paint two coats emulsion to match existing and remove on completion	4,933.00

Additional Council Items	Prov cost	Total Cost (excl VAT)
		122.00
		579.00
		694.00
Additional provision for extra plaster repairs	175	515.00
Sound insulation material	1,000	
Cleaning light fittings and ceiling area	350	
		6,283.00